

The IEX Electromagnetic Variably Polarizing Quasi-periodic Undulator

or Just


The IEX Undulator Intermediate Energy X-ray

By Mark Jaski

Outline

- History
- Specifications and Parameters
- Prototype
- Quasi-periodicity
- Design and Assembly
- Future Plans

History



The CPU in Sector 4

E. Gluskin et al., AIP Conf. Proc. 521, 344 (2000)

- The project started with a request for a device similar to the circularly polarizing undulator (CPU) installed in Sector 4:
 - low photon energies
 - choice of polarizations (linear horizontal & vertical, left and right-handed circular)
- There were to be differences:
 - An option to minimize higher harmonics in the photon spectrum
 - No need for rapid switching between left- and right-handed circular polarizations
- Several possible undulator designs were discussed
 - Apple II (all permanent magnet)
 - Electromagnetic/Permanent magnet
 - Electromagnetic

Specifications

General	Period	12.5	cm
	Gap	10.5	mm
	Periods per device (including end poles)	38	Periods
Horizontal Linear Polarization	Minimum Photon Energy	250	eV
	Required vertical effective field	4514	Gauss
	Effective K Value	5.27	
Vertical Linear Polarization	Minimum Photon Energy	440	eV
	Required horizontal effective field	3308	Gauss
	Effective K Value	3.86	
Circular Polarization	Minimum Photon Energy	440	eV
	Required horizontal and vertical effective field	2340	Gauss
Maximum Allowed 1st and 2nd Integrals	1st integral Bx	50	Gauss-cm
	2nd integral Bx	100,000	Gauss-cm ²
	1st integral By	100	Gauss-cm
	2nd integral By	100,000	Gauss-cm ²
Maximum Allowed Integrated Multipoles	Normal Quadrupole	50	Gauss
	Normal Sextupole	200	Gauss-cm ⁻¹
	Normal Octupole	300	Gauss-cm ⁻²
	Skew Quadrupole	50	Gauss
	Skew Sextupole	100	Gauss-cm ⁻¹
	Skew Octupole	50	Gauss-cm ⁻²

Selected Parameters


General	Period	12.5	cm
	Gap	10.5	mm
	Periods per device (including end poles)	38	Periods
	Length	4.8	m
By Field	Max Achievable Vertical Effective Field	4599	Gauss
	Peak field ¹	5456	Gauss
	Current ¹	47.6	A
	Number of By coils	112	Each
	Number of By Quasi-periodic coils	40	Each
	Total Power of By Coils ¹	4846	Watts
Bx Field	Total Power of By Quasi-periodic coils ¹	1803	Watts
	Max Achievable Horizontal Effective Field	3362	Gauss
	Peak field ¹	3767	Gauss
	Current ¹	50.3	A
	Number of Bx coils	224	Each
	Number of Bx Quasi-periodic coils	80	Each
	Total Power of Bx Coils ¹	8764	Watts
Total Power of Bx Quasi-periodic coils ¹	3220	Watts	

Bx Trim Coils	Peak Current	5.87	A
	Total Power at Peak Current	40	Watts
	Number of Bx trim coils	4 upstream	Each
		4 downstream	Each
By Trim Coils	Peak Current	5.53	A
	Total Power at Peak Current	45	Watts
	Number of By trim coils	2 upstream	Each
		2 downstream	Each
Maximum Achievable Multipole Corrections	DS Skew Dipole	9,021	G-cm
	DS Normal Dipole	13,153	G-cm
	DS Skew Quadrupole	4,251	G
	DS Normal Quadrupole	15,158	G
	DS Normal Sextupole	10,236	G/cm
	DS Skew Octupole	346	G/cm ²
	US Skew Dipole	8,043	G-cm
	US Normal Dipole	13,054	G-cm
	US Skew Quadrupole	4,569	G
	US Normal Quadrupole	15,144	G
	US Normal Sextupole	10,140	G/cm
US Skew Octupole	375	G/cm ²	
Earth Field Corrector	Integrated Field Per Ampere	490	Gauss-cm/A
	Peak Current	8	A
	Total Power at Peak Current	4.5	Watts
	Maximum Temperature of Coils	100	°C

¹At the Max Achievable Effective Field
All fields listed above are calculated values

17 Power Supplies


Prototype General Assembly Exploded View



OPERA 4 Period Model For Prototype

24/Jan/2011 12:59:10

No Coils




Opera

OPERA 4 Period Model For Prototype

24/Jan/2011 12:58:12

Add the Coils

Typically end coils are $\sim \frac{1}{4}$ - $\frac{3}{4}$ - 1 turns



Actual Turns

Bx 11 - 34 - 46


By 15 - 42 - 62

Opera

OPERA 4 Period Model For Prototype

24/Jan/2011 12:57:06


Add Trim Coils



For Beam Steering And Multipole Correction

Opera


IEX Prototype 2 (4 periods)



Major Findings

- Two prototypes were built. The first showed that the cooling scheme would work as calculated.
- During the construction of the first prototype, beam simulations showed that the field roll-off was too large for storage ring injection.
- The magnetic design was modified to make the poles wider so as to reduce the roll-off. Prototype 2 was built.
- Magnetic measurements of the prototype agreed with the calculations, after some adjustment of the assumed magnetic properties.
- Separate power supplies for each end coil provides a means to correct several multipoles.

Quasi-periodicity Suppresses the Higher Harmonics




Flux in linear horizontal polarization mode at 250-eV first-harmonic energy for two different QP patterns with reduced magnetic field at the QP poles (85% of regular field). The higher harmonics are shifted to lower energies with the QP turned on. The energy shift is smaller for the 16-pole pattern (blue dashed curve). The flux of the third harmonic is reduced to $\sim 8\%$ and the second harmonic is reduced to less than 50% for both patterns. The first harmonic is reduced by $\sim 20\%$.

IEX Layout

Air Exhaust ports each end
To the tunnel air handling system
(Marvin Kirshenbaum)

Welded Aluminum
Top Frames




Steel Second Frame

Steel Bottom Frame

IEX Device

Installation in April 2012



4.8 m long
~14,000 lbs

Assembly



Future Plans

- Complete assembly and begin magnetic measurements in January 2012.
- 3 months for magnetic measurements, testing, and creating look-up tables.
- Installation in sector 29 is currently scheduled for the April/May 2012 shut down.
- Development of a fast switching (10 Hz) electromagnetic device is underway.

Acknowledgements

Administrative

Renee Lanham
Michael Oprondek
Romas Senkevicius

Alignment

Bill Jansma
Merrick Penicka

Engineering

Jeff Collins
Chuck Doose
Matt Kasa
Marvin Kirshenbaum
John Sidarous
Eugene Swetin
Emil Trakhtenberg
Greg Wiemerslage

Management

Efim Gluskin
Michael Merritt
Liz Moog
Mohan Ramanathan

Magnet Measurement

Melike Abliz
Isaac Vasserman

Physics

Michael Borland
Roger Dejus
Louis Emery
Suk Kim
Vadim Sajaev
Shigemi Sasaki
Aimin Xiao

Power Supplies and Controls

Boris Deriy
Marty Smith
Ju Wang
Joe Xu

Technician

Ralph Bechtold
Cheryl Bergthold
Susan Bettenhausen
Kurt Boerste
Jack Burke
Joe Gagliano III
Mike Johnson
Thomas Meier
Glenn Moonier
John TerHaar
Ed Theres
Rob Wright

Thank You