

Development and Production of NSLS II by AES MOM Vacuum Group

An overview of the role that the AES-MOM vacuum group contributed to the NSLS II project. A 6-year project (2006 – 2012) started with contributing to final designs focused to weld joints and vacuum certification. Our group then focused on automated weld development, pre-production welding, Q/A measurement, cleaning and testing. After several full size pre-production vacuum chambers we completed and vacuum certified, the group then went into full production of NSLS II completing an average of 8 chambers a month on time and under budget while supporting APS. NSLS II on track to be ready for operation in 2015.

AES-MOM Vacuum Group - Who we are

Staff

- **George Goeppner** – Group Leader
- **Joe Gagliano** – Section Leader
- **John Hoyt** - Engineer
- **Try Leng Kruey** – Engineer
- **Mark Martens** – Chief Technician
- **John Zientek** - Engineer

Technicians

- **Scott Abbeduto**
- **Jack Burke**
- **Cheri Giacomi**
- **Guy Harris**
- **Kevin Knoerzer**
- **Aaron Lopez**
- **Raul Mascote**
- **Wayne Michalek**
- **Russ Otto**
- **Cristen Sarne (CJ)**
- **Robert Wilson**



AES-MOM Vacuum Group - What we do

- **Provide support for all APS vacuum related equipment**
 - Linac, Par, Booster, Storage Ring and Front Ends
- **Provide support for all pneumatic related systems**
 - Gate valves, safety shutters, photon shutters and beamline pneumatic doors
- **Provide support to the USER community**
 - USER Beamlines (vacuum and pneumatic systems)
- **Unique fabrication capabilities in building 382**
 - Aqueous cleaning, robotic welding, inspection of components, vacuum leak checking, high temperature vacuum oven, assembly of critical components, vacuum testing and vacuum certification
- **Services available to all of ANL and DOE laboratories**

Building a Storage Ring

- Contribution
- Development
- Production
 - Inventory
 - Q/A
 - Cleaning
 - Assembly
 - Certification



NSLS II Specifications


- Nominal Energy 3 GeV
- Nominal Current 500 ma

Building 382 - “UHV Vacuum Factory”


- **Complete fabrication facility**
 - Traveler and associated documentation to accompany each component
 - Inspection
 - Aqueous cleaning
 - Baking of vacuum components
 - Welding
 - Assembly and testing
- **Precision advanced arc welding systems**
 - Multi-axis contouring, integrating all welding parameters for a given weld path

Development

- Vacuum chamber material
 - Chamber 6063
 - Transition and Exit port 2219
 - Flange 6061 explosion bond to Stainless steel
- Flange issues during inspection
 - Leaking bi-metal joint
 - Wrong grade of aluminum
 - Porosity
 - Resulted in over 100 flanges recalled




Development




- 8 unique di-pole chamber designs
- 8 unique multi-pole chamber designs
- 3 straight sections to fill in for future ID chambers
- 218 vacuum chambers built

Development - Tooling

- All new tooling was developed by MOM – Vacuum group and fabricated in Central Shops



Development - Tooling





Production - Inventory



- 6 to 8 weeks of parts
- Average 8 chambers a month



Production - Q/A



- Random selection of each part for dimension check
- Go no-go gauge
- Pre weld leak check of Bi-metal flange



Production - Aqueous Cleaning



Production - Traveler

- Every part has documentation to follow it through to final production
- The complete multipage document is scanned to a pdf and filed for future reference

BNL PRODUCTION TRAVELER

Assembly No. 6303
56 Evn

Serial No. 0616

	INITIAL DATE IN	INITIAL DATE OUT	COMMENTS
Chamber Received	52 5/1/11	52 5/1/11	
Chamber Inspected	82 10/26/11	83 10/26/11	
Chamber Pwr Wash Ridoline 18	BF/SA 10/27/11	BF/SA 10/27/11	
Chamber Cleaned Citronox Ultrasonic	BF/SA 10/29/11	BF/SA 10/27/11	
Chamber Welded Water fitting, RF block, Router	DVL 11-2-11	RR 11-14-11	
Check 3 3/8 port with gauge	DVL 11-11-11	DVL 11-11-11	
Chamber Leak Tested	11-14-11 A.L.G.H	11-14-11 G.H.R.L	Found Leak 3 3/8 Repair Leak
BPM Polish	11-14-11 S.P	11-14-11 S.P	
Chamber Post-cleaned Citronox No Ultrasonic	BF/SA 11/15/11	BF/SA 11/15/11	
Chamber Assembly		11/17/11 AL/AL/RM	
Chamber Bakeout	12-1-11 AL/AL/RM	12/3/11 AL/RM	
Chamber Final Leak Check		12/5/11 AL/AL	
Prepare For Shipping		12/5/11 AL/AL/RM	

Production - Traveler

- Inspection
- Leak Check
- Certification test log
- RGA

AES-MOM LEAK CHECK FORM

Information

Serial Number: 4454 Sitter Location: _____
 Part Number or Name: 6.6 Dupole
 Date: 6/22/11 Technician: Al RM
 Leak Detector: 181 Idz #15 Calibrated Leak: 12.6
 Part Description: _____
 Comments: _____

Results

Test Pressure: < 10⁻⁵
 Helium Background: _____ Helium Leak Rate: _____
 Pump Down Time: 10 min
 Comments: No leak

Inspector: Al + RM Date: 6/22/11


WELD PROCEDURE INSPECTION LOG

6.00 X 6.00 Dupole Couplet To Transition

Assembly Number: CHM-220
 Equipment No. 4454 - 1123 4454 - 1181
 Welding Machine Serial No. 11550
 Schedule: Weld Pass BNL6XW1
 Fixture No. 668
 Torch WP-24W Tungsten 2% TH Dia .093 Taper .250 Flat .040
 Stickout 250 Gas Flow 30-40 CFH Gas Mixture 75% HE 25% AR
 Wire Type ER-4043-HQ Wire Dia. .041 Gas Cup No. 6
 Current Override % 111 Voltage Override % 110
 Data Logger No. 4454 - 1122 4454 - 1181

Preparation	Accept	Reject	Comments
Cleaning	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Hand Scraping	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Fit-Up	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Tooling	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pre-Weld Step	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Starting Position	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Tracking (Dry Run)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Worlfeed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Welding	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Weld Tracking	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<u>top side flange 1981 slight rotation</u>

Continued on back of this page



BNL TEST LOG

Chamber No. 571

Assembly			
	Accept	Reject	Comments
Post weld leak check	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Inspect chamber for contamination	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Inspect upstream flanges	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Inspect downstream flanges	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Inspect pump out flange	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Inspect instrumentation flanges	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Inspect absorber flange	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Inspect BFM finish	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Inspect exit port flange	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Bakout				
	Chamber Temperature	Chamber Pressure	Date / Time	Comments
18 degree per hour ramp				
Initial temperature	27.7	7.1E-6	7/26/11	neg
Ramp up to 135 C	135.5	9.3E-6	7/26/11	neg
Hold @ 135 for 16 hours	135.5	9.3E-6	7/26/11	neg
Isolate chamber	117.0	1.2E-7	7/26/11	neg
Ramp down to initial temperature	135.5	9.3E-6	7/26/11	neg
RGA scan	29.0	1.0E-9	7/29/11	neg

Final Leak Check and Prepare for Shipping			
	Accept	Reject	Comments
Final leak check	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Pressure test water channel with He @ 20 PSI	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Tested By: AL G. H. E. #1 Date: 7-20-11
 Approved By: [Signature] Date: 7/25/11

Precision Advanced Arc Welding Systems

- **Manual and Automated welding services**
 - Provide weld development
 - Provide welded components that meet or exceed Mil Spec requirements
- **Components fabricated using automated welding equipment**
 - All aluminum vacuum chambers for APS
 - All aluminum ID vacuum chambers for APS



John Zientek - AES Division - Mechanical Operations and Maintenance Vacuum Group



Components Fabricated at APS

- APS Storage Ring
- BESSY II chambers
- DESY FEL chambers
- SLS chambers
- ESRF chamber
- CLS chambers
- LBL chambers
- KEK chambers
- NSLSII storage ring chambers
- LCLS chambers




Fermi Numi Horn fabricated at Argonne using innovative welding methods to assemble and straighten the Numi Horn for Fermi lab Neutrino Experiment

Production - welding

- Part drawings are used to create programs for the automated welding system
- The process involves several months of development




Final A-joint weld



ITEM	QUANTITY	PART NUMBER	REV	DESCRIPTION OF DESCRIPTION	MATERIAL TYPE	REV
PARTS LIST / BILL OF MATERIALS						
ADVANCED PHOTON SOURCE						
STORAGE RING VACUUM SYSTEMS, CHAMBERS						
CHAMBER, MULTIPLE, MACH. PROTOTYPE						
SR-VA-CHM-2402						
REV	0	0				
SHEET 1 OF 2						

Production - Assembly

NSLS II Chamber



Video
weld
bend



Production - Certification

Vacuum Oven



Vacuum Chamber Testing and Certification



Thank you

- George Goeppner
- Joe Gagliano
- Charles Hetzel - BNL
- Nick Sereno
- MOM Vacuum Group

